Pro-Active and Responsive Facilitation by Interactive,

Single-Window Hub

and Virtuous Environmental





# **Government of India** Ministry of Environment, Forest and Climate Change (Issued by the State Environment Impact Assessment Authority(SEIAA), Maharashtra)

To,

The Technical Director M/S. VILAS JAVDEKAR ECO SHELTERS PVT LTD (POH) 306, Siddharth Towers, Sangam Press Road, Haveli, Pune, Maharashtra -411038

Subject: Grant of Environmental Clearance (EC) to the proposed Project Activity under the provision of EIA Notification 2006-regarding

Sir/Madam.

This is in reference to your application for Environmental Clearance (EC) in respect of project submitted to the SEIAA vide proposal number SIA/MH/MIS/241306/2021 dated 30 Nov 2021. The particulars of the environmental clearance granted to the project are as below.

EC22B038MH191362 1. EC Identification No. SIA/MH/MIS/241306/2021 2. File No.

3. **Project Type** Expansion 4. Category B2

Project/Activity including

8(a) Building and Construction projects 5. Schedule No.

6. Name of Project Residential and Commercial project at Survey Number 111/1/1, village Wakad, Taluka Mulshi, District Pune. by M/s. Vilas Proposed expansion and amendment in


M/S. VILAS JAVDEKAR ECO Name of Company/Organization 7. SHELTERS PVT LTD (POH)

8. **Location of Project** Maharashtra

9. **TOR Date** N/A

The project details along with terms and conditions are appended herewith from page no 2 onwards.

(e-signed) Manisha Patankar Mhaiskar Date: 11/07/2022 **Member Secretary** SEIAA - (Maharashtra)



This is a computer generated cover page.

### STATE LEVEL ENVIRONMENT IMPACT ASSESSMENT AUTHORITY

No. SIA/MH/MIS/241306/2021 Environment & Climate Change Department Room No. 217, 2<sup>nd</sup> Floor, Mantralaya, Mumbai- 400032.

To M/s. Vilas Javdekar Eco Shelters Pvt. Ltd., Survey Number 111/1/1, village Wakad, Taluka Mulshi, District Pune.

> : Environmental Clearance for Proposed expansion and amendment in Subject Residential and Commercial project at Survey Number 111/1/1, village Wakad, Taluka Mulshi, District Pune. by M/s. Vilas Javdekar Eco Shelters Pvt. Ltd.

Reference: Application no. SIA/MH/MIS/241306/2021

This has reference to your communication on the above mentioned subject. The proposal was considered by the SEAC-3 in its 140th meeting under screening category 8 (a) B2 as per EIA Notification, 2006 and recommend to SEIAA. Proposal then considered in 244th (Day-3) meeting of State Level Environment Impact Assessment Authority (SEIAA).

Brief Information of the project submitted by you is as below:-2.

3. Proposal Number	SIA/MH/MIS/241306/2021			
Name of Project	Proposed Expansion and Amendment in the Residential and Commercial project at Survey Number 111/1/1, village Wakad, Taluka Mulshi, District Pune by M/s. Vilas Javdekar Eco Shelters Pvt. Ltd.			
Project category	8(a), B2	· · · · · · · · · · · · · · · · · · ·		
TypeofInstitution	Private			
Project Proponent	Name	M/s. Vilas Javdekar Eco Shelters Pvt. Ltd.		
	Regd. Office 306, Siddharth Towers, Sangam Press Roaddress Kothrud, Pune- 411038			
	Contact number	020-67648000		
	e-mail ankitt.golcha@javdekars.com			
Consultant	Sneha Hi-Tech P	roducts Pvt. Ltd.		
Applied for	Expansion and Am	endment in existing project		
Details of previous EC	Project has received EC letter dated 28.02.2020 vide no. SIA/MH/MIS/121066/2019 for Total Construction area of 1,10,999.99 sq.m. (FSI- 49,620.71 sq.m.+Non FSI- 61,379.28 sq.m.). EC was restricted to total construction area of 86,249.37 sq.m. (FSI- 31,043.58 sq.m.+Non FSI- 55,205.79 sq.m.)			
Location of the project	Survey Number 111/1/1, village Wakad, Taluka Mulshi, District Pune by M/s. Vilas Javdekar Eco Shelters Pvt. Ltd.			
Latitude and Longitude	Latitude: 18°36'30.60"N,			
	Longitude: 73°44'48.92"E			
Total Plot Area(m²)	18,000.00			
Deductions(m <sup>2</sup> )	1873.26			

Net Plot a	rea(m²)	16,126.74						
	FSI area(m²)	84,718.96						
Proposed	non-FSI	45,488.45						
area(m2)		'-	73,700.73					
Proposed T	BUA(m²)	1,30,207.	41					
	approved by			10.2021 (sanctic	n no BP/V	Vakad/12/2021)		
	uthority till date	1001000	ved dated 20.	ro.2021 (Sunotic	,	Valida 12/2021)		
	verage(m²)&%	5483.63 s	a.m 34.00% (	on net plot area	without bas	sement)		
	. 012B0(111 )00 / 0			(on net plot are				
Total Proje	ct Cost(Rs.)	Rs. 327 C		A PRESIDENCE CONTRACTOR				
CER	Activity		Location	Cost(	Rs.)	Duration		
asperMoEF&	&							
CCcircular						general de la companya de la company		
Dated01/05/	20				h. 186			
18								
NA, per Me	morandum 22-65	/2017-IA-II	I dated 25th F	ebruary 2021				
	<b>Building Config</b>					Reason for		
	e following lege					Modification/Cha		
:Floor=F,Pa	arking=Pk,Podi	um=Po,Sti	lt=St,Lower(	Ground=LG,U	pperGro	nge		
	asement=B,Sho							
Previous E	C/Existing Buil	ding	Proposed C	onfiguration				
Building	Configurati	Height	Building	Configurat	Height			
Name	on	(m)	Name	ion	(m)			
Building A	B+L.P+U.P+2	69.95	Wing B	B2+B1+	84.85	Change in		
	1 Floors			Gr./Parking		configuration and		
				Fl.+27 upper		building name		
				floors				
Building B	B+L.P+U.P+2	69.95	Wing C	B2+B1+	84.85	Change in		
	1 Floors			Gr./Parking		configuration and		
				Fl.+27 upper		building name		
Section 1				floors				
Building C	B1+B2+B3+S	69.95	Wing	B3+B2+B1+	44.95	Change in		
l Jaro	T/B+GR+		Residential	Gr. Fl.+13		configuration and		
	1 <sup>ST</sup> /MEZ.+19	en Establishing	+ 300	upper floors		building name		
€	Floors		Commercia					
			1:					
_	Not there in		Wing A	B2+B1+Gr/P	84.85	Newly added		
	EC	Majes.		arking Fl. +				
				27 Upper	kar P			
	<u>.</u>			Floor				
	(				ÿ.			
Club	G+1 floor	7.95	Club house	Part Ground		Change in location		
house	,	'		and part 1st				
HOUSE								
nouse	ł							
nouse				floor of	, i	·		
nouse			·					
nouse			·	floor of				
	Not there in		Multipurpo	floor of Wing B		Newly added		
Multipurp ose hall	Not there in EC	- -	Multipurpo se hall	floor of		Newly added		

			T				1		
Changing rooms	Not the EC	ere in	-	Changin rooms	σι	Gr. Fl. in Open space		Newly added	
Total numb	er of te	enement:	S S			400 nos. Wing. Commerc	of Residential area =	os. for Wings A, B & C, ential & Commercial  2900 sq.mt. se + multipurpose hall)	
Water Bud	lget	Dry Se	ason (CM	D)		Wet Season (	CMD)		
		Fresh V	Vater	395		Fresh Water		395	
	w <sup>1</sup> 1	Recycle	ed (flushi	ng) 203		Recycled (flu	shing)	203	
		Recycle (Garde	ed water ening)	50		Recycled wat (Gardening)	er	0	
	<u> </u>	Swimm	ing Pool	5		Swimming Po	ool	0	
	.5	Total		648	ese updra	Total		598	
		Waste v generat		540		Waste water generation		540	
	<u> </u>	, 11 at							
WaterStora Capacity for	or	Fire Fighting Tank				350 KLD			
Firefighting UGT	g/	Domestic Water Tank				1300 KLD			
Flushing Wa		ing Water	Water Tank		157 KLD				
Sourceofwa	ater	PCMC	/Tanker	water	di 		y di		
Rainwater Harvesting (RWH)		Level o	f the Gro	und water		7 m below gr	ound leve	el	
	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		nd no. of nantity:	RWH tank	(s)	NA THE THE PART OF			
.24 .4		Quantit pits:	y and size	of recharg	e	06 nos., 2 X 2 X 2.5 m			
				anks if any:		NA			
Sewageand		Sewage generation in CMD:			D:	540			
Wastewater		STP technology:				MBBR			
			ty of ST	P (CMD):	<u>şod</u>	545		As,	
Solid Wast		Type				uantity(kg/d) Treatment/disposal			
Managemer	nt	Dry wa			∐ Lab	abor camps are provided on centralized space			
during		Wet wa		Ks ( )	1: .	XM ( )	T		
Construction Phase	on	Constru	Construction waste At		At a	exte		d on site at maximum  nded over to local body	
Solid Wast	 е	Туре			Ou			ent/disposal	
Managemenduring Ope Phase	nt	Dry wa	ste:		950			l over to Authorized	
1 11450		Wet wa	ste:		133	1	Treated	Treated in OWC	

	Hazardous waste:	NA	
	Biomedical waste	At actual (Pandemic waste like PPE, Masks, gloves etc.)	Shall be segregated at decided place and shall be handed over to Authorised vendor for disposal.
	E-Waste	8	Handed over to Authorized recycler for further handling & disposal purpose.
	STP Sludge (dry)	109	Used as manure for gardening
GreenBelt			
Development	Total RG area(r	n²):	1791.86 m <sup>2</sup>
	Existing trees on	The Section of the second seco	Onos.
	Number of trees		202 nos.
	Number of trees		0 nos.
		to be transplanted:	0 nos.
<del></del>	1 (unifoci of trees	to oo transpianteed.	
Power	Source of power	supply:	MSEDCL
	During Constru Load):	ction Phase(Demand	78.25 KW
		on phase (Connected	4696.11 KW
	During	e (Demand load):	2653.23 KW
7 5, - C	Transformer:		4 X 630 KVA + 1 X 500 KVA
	DG set:		3 X 320 KVA
	Fuel used:		HSD
Details of Energy saving	Total Saving = 2 Saving only due	1.83 % to Solar Component = 19	9%
Environmental		Construction	phase
Management plan budget during Construction phase	Type I	Details	Total Cost (Rs. Lakhs)
<i>ў</i>	Capital Cost (Rs. Lakhs)	Site Barricading, Personal Protective Equipment, Site Sanitation- Mobile toilets& Debris Management	30.00 (cost incurred out of above mentioned cost = Rs.15 Lakhs)
	O & M Cost (Rs.	Water for Dust Suppression	2
	Lakhs per annum)	Site Sanitation, Disinfection & Safety	1.5
		Environmental  Monitoring	2

Health Check up	2.5
 Environment	13.20
Management Cell	
total	21.20

Environmental Management plan Budget during Operation phase

Operation pha	ıse	44	ggeneral .
Component	Details	Capit	O&M (Rs.in Lakhs/Y)
		al cost (Rs. Lakhs )	
Storm Water	Connection to external line	1.0	0.1
Sewage treatment	STP Operation and its maintenance	132.2	27.93
Water treatment	Treatment of ground water for its portability	10	0.5
RWH	Recharging existing ground water table	9	0.3
Swimming Pool		28.0	0.6
Solid Waste	Collection Segregation and management of MSW	25.50	7.97
Hazardous waste	NA	NA	NA
e-waste	Collection Segregation and hand over to authorized vendors	-	0.15
Green belt development	Plantation of new trees and	9.13	2.80

		maintenance of existing trees				
	Energy saving	Energy saving measures	125.1 2	2.5		
	Environment al Monitoring	To monitor sustainabilit y of Environment al Infrastructur e		4		
	Environment al Management cell	To monitor on each environment al infrastructure provided		6.4	*	
	Disaster Management	Emergency preparedness plan to develop and implement on site	97.45	25		
	Basement ventilation	Ventilation for basements	110	50		
	Basement pumping + Sewage pumping	Dewatering of basements and pumping of excess treated water upto sewer line	5.42	0.55		
	Biomedical Waste Management	Handling segregation and management of waste like mask, shields, PPE kits etc.	0.5	Considered in	solid waste	
	Total		553.3 5	128.8		
Traffic Management	Required as per	DCR Actua	l Provid	ed	Area per parking (m²)	

4-Wheeler	386	386	32-35
2-Wheeler	2714	2714	
Cycle			
Details of	No		
Court cases/ litigations			
w.r.t. the project and project			
location if any.			

4. Proposal is an expansion of existing construction project. Project has received earlier EC vide letter dated 28.02.2020 for total construction area of 86,249.37 sq.m. (FSI- 31,043.58 sq.m.+ Non FSI- 55,205.79 sq.m.). Proposal has been considered by SEIAA in its 244<sup>th</sup> (Day-3) meeting and decided to accord Environment Clearance to the said project under the provisions of Environment Impact Assessment Notification, 2006 subject to implantation of following terms and conditions-

# **Specific Conditions:**

### A. SEAC Conditions-

- 1. PP to submit Certified compliance report from Regional Office MoEFCC, Nagpur.
- 2. PP to submit the structural stability certificate for the buildings where vertical expansion is proposes.
- 3. PP to provide minimum 30% of total parking arrangement with electric charging facility by providing charging points at suitable places.
- 4. PP to ensure that, the water proposed to use for construction phase should not be drinking water. They can use recycled water or tanker water for proposed construction.

#### **B. SEIAA Conditions-**

- 1. PP to keep open space unpaved so as to ensure permeability of water. However, whenever paving is deemed necessary, PP to provide grass pavers of suitable types & strength to increase the water permeable area as well as to allow effective fire tender movement.
- 2. PP to achieve at least 5% of total energy requirement from solar/other renewable sources.
- 3. PP Shall comply with Standard EC conditions mentioned in the Office Memorandum issued by MoEF& CC vide F.No.22-34/2018-IA.III dt.04.01.2019.
- 4. SEIAA after deliberation decided to grant EC for FSI- 83213.87 m2, Non-FSI- 44769.84 m2, Total BUA- 127983.71 m2. (Plan approval-BP/EC/Wakad/12/2021 dated 28.10.2021).

#### **General Conditions:**

#### a) Construction Phase :-

- I. The solid waste generated should be properly collected and segregated. Dry/inert solid waste should be disposed of to the approved sites for land filling after recovering recyclable material.
- II. Disposal of muck, Construction spoils, including bituminous material during construction phase should not create any adverse effect on the neighbouring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in the approved sites with the approval of competent authority.

- III. Any hazardous waste generated during construction phase should be disposed of as per applicable rules and norms with necessary approvals of the Maharashtra Pollution Control Board.
- IV. Adequate drinking water and sanitary facilities should be provided for construction workers at the site. Provision should be made for mobile toilets. The safe disposal of wastewater and solid wastes generated during the construction phase should be ensured.
- V. Arrangement shall be made that waste water and storm water do not get mixed.
- VI. Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices.
- VII. The ground water level and its quality should be monitored regularly in consultation with Ground Water Authority.
- VIII. Permission to draw ground water for construction of basement if any shall be obtained from the competent Authority prior to construction/operation of the project.
  - IX. Fixtures for showers, toilet flushing and drinking should be of low flow either by use of aerators or pressure reducing devices or sensor based control.
  - X. The Energy Conservation Building code shall be strictly adhered to.
  - XI. All the topsoil excavated during construction activities should be stored for use in horticulture / landscape development within the project site.
- XII. Additional soil for levelling of the proposed site shall be generated within the sites (to the extent possible) so that natural drainage system of the area is protected and improved.
- XIII. Soil and ground water samples will be tested to ascertain that there is no threat to ground water quality by leaching of heavy metals and other toxic contaminants.
- XIV. PP to strictly adhere to all the conditions mentioned in Maharashtra (Urban Areas)
  Protection and Preservation of Trees Act, 1975 as amended during the validity of
  Environment Clearance.
- XV. The diesel generator sets to be used during construction phase should be low sulphur diesel type and should conform to Environments (Protection) Rules prescribed for air and noise emission standards.
- XVI. PP to strictly adhere to all the conditions mentioned in Maharashtra (Urban Areas)
  Protection and Preservation of Trees Act, 1975 as amended during the validity of
  Environment Clearance.
- XVII. Vehicles hired for transportation of Raw material shall strictly comply the emission norms prescribed by Ministry of Road Transport & Highways Department. The vehicle shall be adequately covered to avoid spillage/leakages.
- XVIII. Ambient noise levels should conform to residential standards both during day and night. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase. Adequate measures should be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB/MPCB.
  - XIX. Diesel power generating sets proposed as source of backup power for elevators and common area illumination during construction phase should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all

- proposed DG sets. Use low sulphur diesel is preferred. The location of the DG sets may be decided with in consultation with Maharashtra Pollution Control Board.
- XX. Regular supervision of the above and other measures for monitoring should be in place all through the construction phase, so as to avoid disturbance to the surroundings by a separate environment cell /designated person.

### B) Operation phase:-

- I. a) The solid waste generated should be properly collected and segregated. b) Wet waste should be treated by Organic Waste Converter and treated waste (manure) should be utilized in the existing premises for gardening. And, no wet garbage will be disposed outside the premises. c) Dry/inert solid waste should be disposed of to the approved sites for land filling after recovering recyclable material.
- II. E-waste shall be disposed through Authorized vendor as per E-waste (Management and Handling) Rules, 2016.
- III. a) The installation of the Sewage Treatment Plant (STP) should be certified by an independent expert and a report in this regard should be submitted to the MPCB and Environment department before the project is commissioned for operation. Treated effluent emanating from STP shall be recycled/ reused to the maximum extent possible. Treatment of 100% grey water by decentralized treatment should be done. Necessary measures should be made to mitigate the odour problem from STP. b) PP to give 100 % treatment to sewage /Liquid waste and explore the possibility to recycle at least 50 % of water, Local authority should ensure this.
- IV. Project proponent shall ensure completion of STP, MSW disposal facility, green belt development prior to occupation of the buildings. As agreed during the SEIAA meeting, PP to explore possibility of utilizing excess treated water in the adjacent area for gardening before discharging it into sewer line No physical occupation or allotment will be given unless all above said environmental infrastructure is installed and made functional including water requirement.
- V. The Occupancy Certificate shall be issued by the Local Planning Authority to the project only after ensuring sustained availability of drinking water, connectivity of sewer line to the project site and proper disposal of treated water as per environmental norms
- VI. Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking should be fully internalized and no public space should be utilized.
- VII. PP to provide adequate electric charging points for electric vehicles (EVs).
- VIII. Green Belt Development shall be carried out considering CPCB guidelines including selection of plant species and in consultation with the local DFO/Agriculture Dept.
  - IX. A separate environment management cell with qualified staff shall be set up for implementation of the stipulated environmental safeguards.
  - X. Separate funds shall be allocated for implementation of environmental protection measures/EMP along with item-wise breaks-up. These cost shall be included as part of the project cost. The funds earmarked for the environment protection measures shall not be diverted for other purposes.
  - XI. The project management shall advertise at least in two local newspapers widely

- circulated in the region around the project, one of which shall be in the Marathi language of the local concerned within seven days of issue of this letter, informing that the project has been accorded environmental clearance and copies of clearance letter are available with the Maharashtra Pollution Control Board and may also be seen at Website at Error! Hyperlink reference not valid parivesh nic in
- XII. Project management should submit half yearly compliance reports in respect of the stipulated prior environment clearance terms and conditions in hard & soft copies to the MPCB & this department, on 1st June & 1st December of each calendar year.
- XIII. A copy of the clearance letter shall be sent by proponent to the concerned Municipal Corporation and the local NGO, if any, from whom suggestions/representations, if any, were received while processing the proposal. The clearance letter shall also be put on the website of the Company by the proponent.
- XIV. The proponent shall upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB. The criteria pollutant levels namely; SPM, RSPM. SO2, NOx (ambient levels as well as stack emissions) or critical sector parameters, indicated for the project shall be monitored and displayed at a convenient location near the main gate of the company in the public domain.

# C) General EC Conditions:-

- I. PP has to strictly abide by the conditions stipulated by SEAC& SEIAA.
- II. If applicable Consent for Establishment" shall be obtained from Maharashtra Pollution Control Board under Air and Water Act and a copy shall be submitted to the Environment department before start of any construction work at the site.
- III. Under the provisions of Environment (Protection) Act, 1986, legal action shall be initiated against the project proponent if it was found that construction of the project has been started without obtaining environmental clearance.
- IV. The project proponent shall also submit six monthly reports on the status of compliance of the stipulated EC conditions including results of monitored data (both in hard copies as well as by e-mail) to the respective Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB.
  - V. The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of EC conditions and shall also be sent to the respective Regional Offices of MoEF by e-mail.
- VI. No further Expansion or modifications, other than mentioned in the EIA Notification, 2006 and its amendments, shall be carried out without prior approval of the SEIAA. In case of deviations or alterations in the project proposal from those submitted to SEIAA for clearance, a fresh reference shall be made to the SEIAA as applicable to assess the adequacy of conditions imposed and to add additional environmental protection measures required, if any.
- VII. This environmental clearance is issued subject to obtaining NOC from Forestry & Wild life angle including clearance from the standing committee of the National Board for Wild life as if applicable & this environment clearance does not necessarily implies

that Forestry & Wild life clearance granted to the project which will be considered separately on merit.

- 5. The environmental clearance is being issued without prejudice to the action initiated under EP Act or any court case pending in the court of law and it does not mean that project proponent has not violated any environmental laws in the past and whatever decision under EP Act or of the Hon'ble court will be binding on the project proponent. Hence this clearance does not give immunity to the project proponent in the case filed against him, if any or action initiated under EP Act.
- 6. This Environment Clearance is issued purely from an environment point of view without prejudice to any court cases and all other applicable permissions/ NOCs shall be obtained before starting proposed work at site.
- 7. In case of submission of false document and non-compliance of stipulated conditions, Authority/ Environment Department will revoke or suspend the Environment clearance without any intimation and initiate appropriate legal action under Environmental Protection Act, 1986.
- 8. Validity of Environment Clearance: The environmental clearance accorded shall be valid as per EIA Notification, 2006, amended from time to time.
- 9. The above stipulations would be enforced among others under the Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986 and rules there under, Hazardous Wastes (Management and Handling) Rules, 1989 and its amendments, the public Liability Insurance Act, 1991 and its amendments.
- 10. Any appeal against this Environment clearance shall lie with the National Green Tribunal (Western Zone Bench, Pune), New Administrative Building, 1<sup>st</sup> Floor, D-Wing, Opposite Council Hall, Pune, if preferred, within 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.

Manisha Patankar-Mhaiskar (Member Secretar 3, 114, 1202 2

#### Copy to:

- 1. Chairman, SEIAA, Mumbai.
- 2. Secretary, MoEF & CC, IA-Division MOEF & CC
- 3. Member Secretary, Maharashtra Pollution Control Board, Mumbai.
- 4. Regional Office MoEF & CC, Nagpur
- 5. District Collector, Pune.
- 6. Commissioner, Pimpri Chinchwad Municipal Corporation
- 7. Regional Officer, Maharashtra Pollution Control Board, Pune.